Vol. 06, No. 4 (2024) 1621-1632, doi: 10.24874/PES06.04.021

Proceedings on Engineering Sciences

www.pesjournal.net

NAVIGATING THE LANDSCAPE OF INNOVATIVE TECHNOLOGIES IN CONSTRUCTION PROJECT MANAGEMENT: A COMPREHENSIVE REVIEW

Houljakbe Houlteurbe Dagou[1]
Asli Pelin Gurgun
Kerim Koc
Handan Kunkcu

Received 08.02.2024.
Received in revised form 13.06.2024.
Accepted 09.07.2024.
UDC – 001.895:624.04

Keywords:

Construction Project Management, Technology Integration, Building Information Modeling (BIM), Artificial Intelligence (AI) in Construction, Emerging Technologies in Construction

A B S T R A C T

This literature review extensively explores the evolving integration of cutting-edge technologies within the realm of construction project management. The advent of innovative tools such as building information modeling (BIM), artificial intelligence (AI), the Internet of Things (IoT), and various digital collaboration platforms has triggered a profound transformation in the construction industry. Through a thorough analysis of academic literature, industrial case studies, and empirical research, this review critically assesses the multifaceted impacts of these technologies, emphasizing their contributions to enhancing efficiency, accuracy, and the overall management of intricate projects.

By delving into the scholarly landscape, the study illuminates how BIM has fundamentally reshaped project planning and execution, fostering improved collaboration and decision-making processes. The review meticulously examines the role of AI in predictive analytics and resource optimization, highlighting the operational enhancements facilitated by IoT implementations in areas such as real-time monitoring and security management. Furthermore, the review investigates the synergies arising from the integration of these technologies, particularly in advancing integrated project delivery (IPD) and bolstering collaborative methodologies.

Identifying emerging trends, such as the utilization of augmented reality (AR) and virtual reality (VR), the review underscores their potential as transformative elements shaping the future of the construction industry. In addition to synthesizing current knowledge, this review identifies gaps in existing research and suggests avenues for future studies. Its overarching goal is to provide a nuanced understanding of the pivotal role played by technology integration in reshaping construction project management, thereby offering valuable insights for academics, industry professionals, and policymakers alike.

© 2024 Published by Faculty of Engineering

[1] Corresponding author: Houljakbe Houlteurbe Dagou
Email: dagoucharles@gmail.com

1. INTRODUCTION

The construction industry is undergoing a significant transformation in its project management practices, primarily driven by integrating innovative technologies. This evolution marks a shift away from traditional, often manual, methodologies toward a more sophisticated approach that harnesses the power of cutting-edge technologies. Several factors fuel this change, including the pressing need for enhanced efficiency, greater precision, and a responsive strategy to meet the escalating complexity of construction projects (Chen et al., 2023; Sepasgozar et al., 2023; Taboada et al., 2023, Eker & Akdogan Eker 2023; Unegbu et al., 2021).

The primary objective of this industry transformation is to recognize and address the limitations inherent in conventional construction practices. While these practices have been reliable, they frequently fall short of meeting the increasing demands for scalability, adaptability, and sustainability, particularly in intricate construction projects. Consequently, the industry is progressively embracing a range of emerging technologies such as Building Information Modeling (BIM), Artificial Intelligence (AI), Internet of Things (IoT), and advanced digital collaboration platforms. This paradigm shift not only refines existing methodologies but fundamentally redefines project management processes within the construction sector (Gal et al., 2018).

An exemplar of this transformation is the integration of BIM, providing a multi-dimensional digital representation of a project's physical and functional characteristics. This fosters an integrative and collaborative project management environment. Furthermore, the utilization of AI and machine learning is gaining traction to obtain predictive information, optimize resource allocation, and enhance decision-making processes. The real-time monitoring and data analysis capabilities of IoT technologies offer valuable insights into site conditions and operational efficiency (Bahroun et al., 2023; Liu et al., 2023; Tsygankov et al., 2023; Regona et al., 2023).

This strategic shift towards leveraging innovative technologies in construction project management underscores the industry's commitment to addressing contemporary challenges, including environmental sustainability, regulatory compliance, and the imperative to adapt swiftly in a dynamic global market.

The objective of this literature review is to critically assess the role and impact of innovative technologies in the construction industry, specifically within the realm of project management. Through a systematic analysis of current academic literature, industrial case studies, and empirical reports, this review aims to provide a scholarly perspective on the transformative influence of these technologies. It seeks to unravel the complexities, challenges, and potential trajectories associated with technological integration in construction project management, thereby contributing to the ongoing academic discourse in this rapidly expanding field (Hardardottir and Moller 2023).

2. PREAMBLE AND ENVIRONMENT

2.1 Management of projects in antiquity

Throughout history, project management, marked by successes amid complexity, lacked documentation. In the 1950s, systematic tools emerged, notably influenced by the U.S. Navy and projects like the Manhattan Project. The 1960s moon landing and 1970s tech facilitated project management software. By the 1990s, tools like PRINCE2 and CCPM emerged. The new millennium saw academic degrees, making project management mainstream amid global challenges (Seymour & Hussein 2014; Arici & Sahin Gok 2024).
Mark Kazak-Holland contends in "The History of Project Management" that projects predate the 20th century, challenging misconceptions about historical projects, budgets, workforce, timelines, and concepts (Pitsi 2018).

While historical projects yielded remarkable results, scant documentation exists due to various factors. Upper society prioritized outcomes over creation methods, and craftsmen, responsible for execution, often kept methods secretive within specific tribes or families across generations (Marnewick and Marnewick 2020; Picciotto 2020; Piraveenan 2019). Y. C. Chiu, in 'A History of Ancient Projects,' explains the scarcity of project management documentation. He contends that, unlike well-documented professions, the term "project" is absent in ancient texts, making the field elusive (Seymour and Hussein 2014).

2.2 Origins of Modern Project Management

Y. C. Chiu, in "Introduction to the History of Project Management," designates Henri Fayol and Henry Gantt as the progenitors of Project Management, highlighting their pivotal roles in its development (Daniel et al., 2023; Hunke & Waibel 1995).

Although opinions may differ, consensus exists on the substantial contributions of both Fayol and Gantt to the management field. Fayol, a French engineer (1841-1925), led a pivotal iron and steel company, focusing on management issues amid pre-World War I rearmament (Parker 2014). Fayol identified five universal management functions: planning, organizing, commanding, coordinating, and controlling. Despite criticism for oversimplification, his 14 principles guide effective execution. While contested, recent findings reinforce Fayol's enduring relevance, standing the test of time (Fells 2000).

Henry Gantt, the second forefather of modern project management, was an American engineer and consultant (1861-1919), renowned for the Gantt chart. These charts, essential in modern project management, acknowledge the advantages of breaking down large projects into manageable tasks and recognizing task dependencies. Despite Karol Adamieckic's earlier concept called the Harmonogram in 1986, which went unrecognized in the West due to language barriers, Gantt's charts gained prominence around 1910-1915. Used in World War I and Hoover Dam's construction, they became synonymous with Gantt's name, even though their origins are debatable. Today, Gantt charts remain a crucial tool in a project manager's toolkit (Bloom & Reenen 2013).

Snyder and Kline (1987) assert that the modern project management era commenced in 1958 with the emergence of CPM/PERT, marking a pivotal advancement. Developed in distinct fields—the Navy and the chemical industry—CPM/PERT played a crucial role. The U.S. Navy's Polaris project, involving submarine-launched ballistic missiles in 1958, notably contributed to the development of the Program Evaluation Review Technique (PERT). PERT, adept at handling complex and uncertain project schedules, gained widespread use. Concurrently, the Critical Path Method (CPM) originated at E. I. du Pont de Nemours Company during a significant chemical plant construction. Initially called Project Planning and Scheduling (PPS), it later evolved into the widely recognized CPM method, addressing the need for accurate project cost and time estimation (Malega 2019; Seymour and Hussein 2014).

3. SYSTEMATIC ANALYSIS OF TECHNOLOGY INFLUENCES

The infusion of cutting-edge technologies into the construction industry, specifically in the realm of project management, has significantly transformed this sector. The profound implications of this integration can be systematically assessed across various domains:

3.1 Efficiency and Productivity:

Integration of task automation and advanced resource management tools notably heightened operational efficiency and productivity. The quantitative measures of success included a reduction in working hours, concurrently resulting in a significant upswing in production output, illustrating the positive impact of these enhancements (Khanzadi et al., 2020).

3.2 Risk Management:

Advanced analytical tools have revolutionized risk management by refining processes for identification, analysis, and mitigation. These tools have substantially minimized the likelihood of project delays and cost overruns, evident in the decreased occurrence of setbacks in technologically advanced projects. The integration of these tools underscores a proactive approach to risk management, ensuring a more resilient and efficient execution of projects in the face of potential challenges (Ahmad et al., 2018; Eifrig, 1972).

3.3 Collaboration and Communication:

The integration of technologies like BIM has revolutionized collaboration among stakeholders, ensuring alignment with project objectives and enabling real-time adjustments. This transformation has yielded measurable outcomes, including a notable reduction in miscommunication incidents and improved alignment in project execution. The use of BIM facilitates a more dynamic and synchronized approach, enhancing the overall coordination among stakeholders. Measurable improvements are evident in the reduced occurrence of miscommunication issues, contributing to smoother project workflows. Real-time adjustments made possible by these technologies further support efficient collaboration and help maintain alignment with project goals. In essence, the integration of such technologies has significantly elevated the effectiveness of stakeholder collaboration in project management (Xue et al., 2014).

3.4 Data-Driven Decision Making:

Decision-making processes are evolving from intuition to data-driven approaches, utilizing AI and big data analytics. This shift emphasizes precision and informed decision-making across various domains. Relying on empirical data and predictive modeling establishes a robust foundation for strategic decision-making. AI and big data integration empower decision-makers to extract insights from vast datasets, fostering a deeper understanding of complex scenarios. This data-driven approach enhances decision accuracy, encourages proactive strategies, and introduces foresight to anticipate outcomes, marking a paradigm shift toward sophisticated decision-making in dynamic, data-rich environments (Li et al., 2022; Provost & Fawcett 2013; Sarker 2021).

4. EMERGING PATTERNS AND SECTOR REQUIREMENTS: A PROACTIVE EXAMINATION

Current trends in construction project management are increasingly emphasizing enhanced digitalization and the incorporation of intelligent systems. These trends underscore a widespread industry demand for globalization, adaptability, and sustainability. The shift towards digitalization signifies a collective recognition within the industry of the benefits derived from advanced technological integration. Embracing intelligent systems aligns with the industry's

overarching goals of operating on a global scale, responding to dynamic changes, and promoting sustainable practices. The evolving landscape of construction project management reflects a strategic commitment to staying abreast of contemporary needs and leveraging technology for long-term viability.

4.1 Sustainably Construct

The focus on green technologies and sustainable practices is driven by the goal to reduce the environmental impact of construction activities. This commitment is reinforced by growing regulatory requirements and heightened societal expectations. The construction industry is increasingly compelled to adopt eco-friendly approaches to align with these mandates and meet the evolving standards of environmental responsibility. Emphasizing sustainability is not only a response to regulations but also reflects a broader acknowledgment of the need for responsible and eco-conscious construction practices. The shift towards greener technologies signifies a proactive stance in addressing environmental concerns and fostering a more sustainable future. Regulatory pressures and societal demands are key drivers influencing the construction sector's transition towards environmentally friendly practices. The industry's responsiveness to these factors signals a collective effort to achieve a more sustainable and environmentally responsible built environment. Overall, the integration of green technologies and sustainable practices represents a strategic response to both regulatory imperatives and the evolving expectations of society (Brockmann et al., 2016).

4.2 Adaptive Project Management

In modern construction projects, the dynamic nature of the industry underscores the critical importance of flexibility and adaptability in project management. These qualities are essential for navigating through changing scenarios and addressing unforeseen challenges that frequently arise during a project. The ability to adapt ensures that project teams can respond effectively to unexpected circumstances, maintaining progress and minimizing disruptions. Flexibility in project management allows for agile decision-making and strategic adjustments, aligning the project with evolving requirements and conditions. Ultimately, the recognition of flexibility and adaptability as pivotal elements in project management reflects an understanding of the unpredictable nature of construction projects and the necessity for responsive approaches (Zhu & Mostafavi 2017).

4.3 Globalized Project Execution

In the context of globalization, it is crucial to possess the capability to manage projects across diverse geographies, each characterized by unique regulatory and environmental conditions. The imperative for a versatile and informed approach to project management arises from the challenges presented by varying global contexts. Successfully navigating these diverse landscapes requires a keen understanding of regional regulations and environmental factors that can significantly impact project outcomes. The ability to adapt strategies and methodologies to fit the specific demands of different geographies becomes a fundamental aspect of effective global project management. Ultimately, a versatile and well-informed approach is essential for achieving success in projects that span a range of regulatory and environmental conditions worldwide (Botta et al., 2016; Lee & Lee 2015).

5. ROLE OF BUILDING INFORMATION MODELING (BIM) IN PROJECT MANAGEMENT

5.1 Inspection and Progression

BIM has brought about a paradigm shift in the management of construction projects, signifying a profound change in methodologies. This transition involves moving away from traditional two-dimensional planning and design approaches, marking the introduction of a comprehensive three-dimensional modeling process. BIM, far beyond being just a tool, serves as an integrative mechanism. It facilitates the creation and management of digital representations encompassing both the physical and functional characteristics of construction projects. This transformative approach extends beyond the mere application of technology and fosters a holistic understanding of project elements through a dynamic and interactive modeling process. In essence, BIM represents a revolutionary departure from conventional practices, offering a more comprehensive and integrated means of managing construction projects (Suermann, 2009).

The historical development and progression of BIM can be traced back to the 1970s when early modeling software first emerged. However, its profound significance was fully recognized in the early 2000s when the construction industry began to comprehend its potential for improving project visualization, coordination, and information management. Over the years, BIM has evolved significantly, expanding beyond its initial capabilities (Borkowski 2023).

In the contemporary context, BIM goes far beyond mere geometric data representation. It has transformed into a comprehensive tool that addresses various aspects of construction projects. These aspects include spatial relationships, light analysis, geographic information, as well as the quantities and properties of diverse building components. This expanded scope allows BIM to provide a holistic view of a project,

facilitating better decision-making and project management (Ma 2021).

The evolution of BIM is marked by a shift from a basic modeling tool to a sophisticated system that integrates multiple dimensions of information. It serves as a dynamic platform that not only enhances visualization but also enables a deeper understanding of the complex interdependencies within construction projects. The versatility of BIM has made it an indispensable asset in the modern construction industry, contributing to improved efficiency, collaboration, and overall project outcomes (Al Hattab 2021).

As BIM continues to advance, its applications are expected to broaden further, incorporating emerging technologies and addressing increasingly complex project requirements. The historical trajectory of BIM underscores its transformative impact on construction project management, from its early roots in modeling software to its status as a multifaceted tool shaping the future of the industry (Khudhair et al., 2021).

5.2 Impact on Project Management

Enhancing Collaboration and Coordination: BIM has a profound impact on construction project management by fostering unprecedented levels of collaboration and coordination among key stakeholders such as architects, engineers, and contractors. Serving as a shared platform for knowledge and resource management, BIM plays a crucial role in early conflict detection and resolution, thereby reducing the incidence and cost implications of rework. This collaborative aspect of BIM significantly contributes to smoother project execution (Akponeware & Adamu 2017).

Revolutionizing Efficiency in Design and Construction: BIM's capability to enable precise project visualization right from the planning stages has led to a dramatic enhancement in the accuracy and efficiency of both design and construction processes. This extends to improved resource management and logistics during the construction phase, streamlining the overall project timeline. By providing a comprehensive and integrated view of the project, BIM allows for more informed decision-making, leading to optimized design solutions and resource allocation. The efficiency gains achieved through BIM not only save time and resources but also contribute to a more sustainable and cost-effective approach to construction project management (Alizadehsalehi et al., 2020).

5.3 Case Studie and Application

BIM's effectiveness in managing intricate construction processes is underscored by its successful implementation in large-scale and complex projects worldwide. Notable examples include the Shanghai Tower in China and the New Royal Adelaide Hospital in Australia, where BIM played a pivotal role in optimizing project management and ensuring successful outcomes (Liao et al., 2022).

Diverse Application Spectrum: BIM showcases its versatility through a broad spectrum of applications, spanning architectural planning, structural engineering, and MEP (Mechanical, Electrical, and Plumbing) coordination. Its reach extends beyond the construction phase to encompass comprehensive facility management, illustrating its capacity to address diverse facets of the project lifecycle. These exemplary applications of BIM in various domains highlight its adaptability and effectiveness across the entire spectrum of construction-related disciplines (Gal et al., 2018).

5.4 Envisioning the Future Paths and Possibilities

The future of Building Information Modelling (BIM) is closely linked to its integration with other advanced technologies. This integration includes the use of Artificial Intelligence (AI) to enhance predictive analytics, Virtual Reality (VR) to provide immersive project visualization experiences, and Internet of Things (IoT) for seamless real-time data integration and monitoring. The combination of BIM with these emerging technologies is expected to transform the landscape of construction project management (Siccardi & Villa 2023).

In addition to technological integration, BIM is playing an increasingly pivotal role in advancing sustainability within the construction industry. There is a growing trend of leveraging BIM to promote eco-friendly practices in construction processes. It serves as a valuable tool in optimizing resource utilization, reducing waste, and ensuring that projects align with green building standards. Consequently, BIM's integration with sustainability initiatives contributes significantly to enhancing the overall eco-consciousness and environmental impact of construction projects (Datta et al., 2023).

This dual trajectory, involving both technological integration and sustainability advancement, positions BIM at the forefront of shaping the future of construction management. As BIM becomes more intertwined with emerging technologies, it is expected to enhance its capabilities, providing construction professionals with innovative tools and methodologies for more efficient and sustainable project execution. The collaborative synergy between BIM and these technologies not only holds promise for increased efficiency but also reinforces the industry's commitment to environmental responsibility and sustainable construction practices (Allen & Shakantu 2016).

6. ARTIFICIAL INTELLIGENCE (AI)

AI's integration into construction management marks a significant technological advancement. In this domain, AI encompasses a wide range of applications, including sophisticated machine learning algorithms for analyzing data patterns and advanced robotics for automating tasks. The incorporation of AI introduces transformative capabilities that extend across various aspects of construction processes. This integration signifies a pivotal shift in how technology is applied to enhance efficiency and automation within the construction industry (NOOR 2020).

6.1 Key Sectors for the Deployment of Artificial Intelligence

Design Optimization: Harnessing AI algorithms for architectural design improvement, these tools strike a balance between aesthetic appeal and functional practicality. They consider intricate variables such as environmental impact and material efficiency to enhance the overall quality of architectural designs (Cummins et al., 2022; McAllister et al., 2005; Yang & Tarng 1998).

Predictive Maintenance: Deploying machine learning models enables the anticipation of maintenance needs, effectively mitigating equipment downtime and extending operational lifespans. This proactive approach to maintenance ensures a more reliable and efficient operational environment (Cao et al., 2022; Çinar et al., 2020; Ran et al., 2019).

Efficient Supply Chain Management: AI plays a pivotal role in streamlining logistics and supply chain processes, optimizing material availability, and ensuring timely project execution. By leveraging AI capabilities, construction projects benefit from enhanced efficiency and coordination throughout the supply chain, contributing to overall project success (Alshurideh et al., 2022; Baryannis et al., 2019).

6.2 Impact of AI on Modern Construction Practices

Leveraging Predictive Analytics for Project Execution Enhancement: AI's predictive analytics play a pivotal role in anticipating project trajectories, facilitating proactive planning, and enhancing risk management. These analytics encompass a broad spectrum of factors, incorporating elements such as meteorological conditions, resource availability, and workforce dynamics. By utilizing AI's predictive capabilities, construction teams gain valuable insights into potential challenges and opportunities throughout the project lifecycle. This foresight allows for strategic decision-making and the implementation of preemptive measures to optimize project outcomes. In essence, the integration of predictive analytics through AI brings a holistic approach to project management, providing a more informed and proactive foundation for successful execution. The multifaceted insights derived from AI-driven analytics contribute to a refined and efficient project execution process (Xue et al., 2014).

Enhancing Scheduling and Safety through AI Optimization: AI systems play a crucial role in fine-tuning project scheduling, maximizing the utilization of resources while prioritizing safety measures. These systems proactively identify potential hazards, advocating preventive strategies to minimize risks and enhance overall safety. By integrating AI-driven optimization, project scheduling becomes more efficient, ensuring the timely allocation of resources and reducing the likelihood of accidents or safety incidents. The proactive hazard identification provided by AI contributes to a safer working environment, aligning with industry standards and regulations. Ultimately, the integration of AI optimization in scheduling and safety measures brings about a comprehensive improvement in project management practices (Abduljabbar et al., 2019; Tang et al., 2001).

Attaining Financial Viability with AI-Enhanced Cost Management: AI tools contribute to precise budgeting and effective cost control mechanisms by analyzing historical data and market trends. Through this analysis, AI fosters financially sustainable project planning, ensuring a comprehensive understanding of budgetary requirements. The integration of AI-driven cost management enhances the accuracy of financial projections, enabling construction teams to make informed decisions based on reliable data. This not only streamlines the budgeting process but also helps identify potential cost-saving opportunities and optimize resource allocation. In essence, the utilization of AI in cost management ensures a more robust and financially viable approach to construction projects (NOOR 2020).

7. INTERNET OF THINGS (IOT)

The application of the Internet of Things (IoT) in the construction sector involves creating a network of physical devices equipped with sensors, software, and various technologies. These interconnected devices facilitate communication and data exchange with other systems via the internet. The result is the provision of real-time insights across a diverse range of construction aspects. By integrating IoT, construction processes become more interconnected and efficient, allowing for enhanced monitoring and analysis. Ultimately, the incorporation of IoT in construction brings about a transformative approach to managing and optimizing various facets of the construction industry.

7.1 Advantages and Practical Implementations of IoT in Construction

IoT devices enable continuous monitoring and real-time data flow from construction sites, providing vital

information on structural integrity, environmental conditions, and machinery status. This data ensures informed decision-making, enhancing safety and operational efficiency. Monitoring worker health metrics elevates safety standards, while automated tracking processes optimize resource and machinery usage, boosting productivity. The integration of IoT in construction transforms industry practices, offering a comprehensive solution for safety management and operational optimization. Swift responses to issues, facilitated by real-time data collection, foster a proactive construction management approach. The continuous feedback loop established by IoT contributes to ongoing process improvements, creating a dynamic construction ecosystem. The symbiotic relationship between continuous monitoring and data-driven insights showcases the multifaceted advantages of incorporating IoT technology into construction practices (Cheng & Teizer 2013; Shi & Abdel-Aty 2015; Tang et al., 2019).

IoT facilitates proactive maintenance and efficient asset management by enabling predictive maintenance of machinery. Through IoT, equipment failures are anticipated and prevented, leading to enhanced reliability and longevity of assets. Technology plays a pivotal role in optimizing asset utilization by providing real-time insights into the performance and condition of machinery. This proactive approach to maintenance ensures that potential issues are addressed before they escalate, minimizing downtime and improving overall operational efficiency. In summary, IoT's contribution to proactive maintenance and asset management marks a significant advancement in preventing disruptions and maximizing the utilization of valuable resources (Yan et al., 2017; Zonta et al., 2020).

7.2 Obstacles in IoT Deployment and Data Governance

The extensive data collection of IoT devices emphasizes the crucial need for robust data security and privacy measures. Integrating numerous IoT devices into existing construction systems poses complexity, requiring careful consideration for seamless compatibility. Copious data produced by these devices necessitates advanced analytics tools for meaningful insights, presenting challenges in data management. The sheer volume of IoT-generated data demands sophisticated analytics for actionable insights, adding to the challenge of effective data management. Ensuring the harmonious integration of diverse IoT devices within construction systems is a challenging task, requiring strategic planning. The intricate process involves compatibility assurance and careful incorporation of various IoT devices into established construction systems. Effective measures for data security and privacy are paramount given the vast scope of data handling and transmission in IoT devices (Allioui & Mourdi 2023).

8. MERGING TECHNOLOGIES AND COOPERATIVE STRATEGIES IN CONSTRUCTION

8.1 Unified Fusion of Building Information Modeling (BIM), Artificial Intelligence (AI), and Internet of Things (IoT) in Construction

In the present era of construction project management, a discernible shift towards integrating advanced technologies is apparent. This integration, involving Building Information Modeling (BIM), Artificial Intelligence (AI), and the Internet of Things (IoT), signifies a substantial convergence of digital, analytical, and physical technologies. It transcends mere tool additions, constituting a transformative amalgamation that elevates efficiency, accuracy, and collaboration in construction projects. This convergence marks a revolution in traditional practices, inaugurating an era where data-driven insights and real-time information stand as the cornerstones of project management (Pan & Zhang 2021a; Patil 2019).

The synergy among BIM, AI, and IoT establishes a robust framework within the construction sector. BIM, with its exhaustive modeling capabilities, offers a comprehensive digital representation of the physical and functional aspects of a construction project. When coupled with AI's predictive analytics, foreseeing project outcomes and potential challenges, and IoT's real-time monitoring capabilities, a potent triad emerges. This triad facilitates a holistic approach to construction project management, enriching decision-making processes and enhancing operational efficiency through continuous feedback and adaptive strategies. The collaborative integration of these technologies transcends traditional boundaries, fostering a dynamic and data-driven paradigm in the realm of construction project management (Pan & Zhang 2021b; Rane 2023).

8.2 Influence on Collaborative Project Execution and Integrated Project Delivery (IPD)

The convergence of BIM, AI, and IoT profoundly influences the concept and execution of Integrated Project Delivery (IPD), a project delivery method meticulously designed to harmonize the interests, objectives, and practices of all stakeholders engaged in a construction project. This collaborative approach, when enhanced with integrated technologies, establishes an unparalleled level of coordination and transparency, fostering a more synchronized workflow where all parties are not only well-informed but active contributors to the decision-making process (Lawal and Nawari 2023; Sepasgozar et al., 2023).

The incorporation of these technologies revolutionizes the collaborative landscape in construction projects.

BIM acts as a centralized platform, providing accessible project information to all stakeholders and nurturing a shared understanding and vision. AI algorithms analyze this shared data, offering predictive insights and facilitating proactive measures to address potential issues. Concurrently, IoT ensures real-time data collection and monitoring, guaranteeing immediate awareness of the project's progress and any emerging issues, which can be collaboratively addressed. This integration thus enables a more dynamic and responsive project management approach, empowering architects, engineers, contractors, and clients to collaborate more effectively and efficiently (Ali et al., 2022).

9. EMERGING DEVELOPMENTS AND ADVANCEMENTS IN CONSTRUCTION TECHNOLOGY

The construction sector is currently undergoing a significant transformation, driven by the integration of innovative technologies. At the forefront of this evolution are Augmented Reality (AR), Virtual Reality (VR), and drones, collectively promising a vibrant future for construction technology. AR and VR play pivotal roles by introducing immersive experiences and simulations that greatly contribute to project visualization and planning. Simultaneously, drones play a crucial role by providing aerial insights and capabilities for site surveillance. The potential impact of these emerging technologies is nothing short of transformative, as they are expected to comprehensively reshape various facets of construction processes. This transformation spans from the initial design stages, where AR and VR enhance visualization and planning, to ongoing monitoring phases, thereby significantly enhancing precision and efficiency throughout the construction lifecycle (Valavanidis & Valavanidis 2020; Durojaye et al., 2023; Manzoor et al., 2021).

Drones take center stage in the technological shift, poised to revolutionize traditional site surveys and inspections in the construction industry. Going beyond surveillance, drones have emerged as a cost-effective and highly accurate alternative for data collection. This innovative application streamlines data acquisition, introducing unprecedented efficiency and accuracy, marking a substantial advancement in construction technology. The notable focus on drones anticipates a transformative impact on construction processes. The role of drones extends beyond mere surveillance, offering a cost-effective and highly accurate alternative for data collection in the construction industry. This novel application not only streamlines data acquisition processes but also introduces unprecedented levels of efficiency and accuracy, marking a significant advancement in construction technology. As these technologies continue to mature, their synergistic integration is anticipated to propel the construction industry into a new era of productivity and effectiveness. The transformative potential of drones in traditional site surveys and inspections is a notable aspect of the ongoing technological shift in the construction sector (Choi et al., 2023; Mahajan 2021; Rao et al., 2022).

10. CONCLUSIONS

The convergence of cutting-edge technologies, including Building Information Modeling (BIM), Artificial Intelligence (AI), and the Internet of Things (IoT), has acted as a powerful catalyst, instigating transformative changes in the realm of construction project management. This comprehensive review delves into how the synergistic integration of these technologies has ushered in unparalleled efficiencies, accuracy, and collaborative dynamics within the field. The shift from conventional methodologies to a more data-driven and interconnected approach is not merely a change in tools and techniques; it represents a fundamental reimagination of project management paradigms (Schwertner 2017).

The adoption of these innovative technologies carries profound implications for the construction industry, signifying a move towards more transparent, integrated, and proactive project management strategies. However, this transition is not without its challenges, encompassing concerns such as ensuring data security, effective integration of diverse technological systems, and the development of a workforce proficient in these new technologies. Despite these obstacles, the potential benefits, including streamlined project timelines, cost efficiencies, and enhanced safety protocols, serve as compelling incentives for the industry's continued technological progression (Ghaffarianhoseini et al., 2017).

This technological transition opens numerous avenues for future research, each critical for the ongoing evolution of the construction sector. Key areas for exploration include investigating effective methodologies for seamlessly integrating various technologies within construction project management, delving into the ethical implications and security challenges associated with AI and IoT in construction, examining the impact of technology on the construction workforce and emerging skill requirements, exploring the role of technology in promoting sustainable construction practices, particularly in resource optimization and environmental conservation, and undertaking longitudinal studies to assess the enduring impacts of technological integration on construction project outcomes and industry standards (Ghobakhloo et al., 2023; Tan & Taeihagh 2021).

In summary, the integration of BIM, AI, and IoT signifies a pivotal moment in construction project management, heralding a future characterized by enhanced precision, efficiency, and environmental

consciousness. Navigating this technologically rich landscape demands continuous industry research, adaptation, and skill development. The key lies in harnessing the full spectrum of opportunities offered by these advancements, ensuring that construction projects not only meet heightened standards of accuracy and efficiency but also embrace environmentally conscious practices. The industry's ability to embrace and evolve with these integrated technologies will define its success in delivering projects that align with contemporary demands and sustainable principles.

References:

Abduljabbar, R., Dia, H., Liyanage, S., & Bagloee, S. A. (2019). Applications of artificial intelligence in transport: An overview. *Sustainability*, *11*(1), 189.

Ahmad, Z., Thaheem, M. J., & Maqsoom, A. (2018). Building information modeling as a risk transformer: An evolutionary insight into the project uncertainty. *Automation in Construction*, *92*, 103-119.

Akponeware, A. O., & Adamu, Z. A. (2017). Clash detection or clash avoidance? An investigation into coordination problems in 3D BIM. *Buildings*, *7*(3), 75.

Al Hattab, M. (2021). The dynamic evolution of synergies between BIM and sustainability: A text mining and network theory approach. *Journal of Building Engineering*, 37.

Ali, K. N., Alhajlah, H. H., & Kassem, M. A. (2022). Collaboration and risk in building information modelling (BIM): a systematic literature review. *Buildings*, *12*(5), 571.

Alizadehsalehi, S., Hadavi, A., & Huang, J. C. (2020). From BIM to extended reality in AEC industry. *Automation in construction*, *116*, 103254.

Allen, C., & Shakantu, W. (2016). The BIM revolution: a literature review on rethinking the business of construction. *WIT Transactions on Ecology and the Environment*, *204*, 919-930.

Allioui, H., & Mourdi, Y. (2023). Exploring the full potentials of IoT for better financial growth and stability: A comprehensive survey. *Sensors*, *23*(19), 8015.

Alshurideh, M. T., Al Kurdi, B., Alzoubi, H. M., Ghazal, T. M., Said, R. A., AlHamad, A. Q., Hamadneh, S., Sahawneh, N., & Al-kassem, A. H. (2022). Fuzzy assisted human resource management for supply chain management issues. *Annals of Operations Research*. Springer US..

Arici, T., & Sahin Gok, M. (2024). Ambiguous effect of environmental turbulence on innovation and performance: Analyzing technology sectors. *Journal of Innovations in Business and Industry*, *2*(1), 13–28. https://doi.org/10.61552/JIBI.2024.01.003

Bahroun, Z., Anane, C., Ahmed, V., & Zacca, A. (2023). Transforming education: A comprehensive review of generative artificial intelligence in educational settings through bibliometric and content analysis. *Sustainability (Switzerland)*, *15*(17).

Baryannis, G., Validi, S., Dani, S., & Antoniou, G. (2019). Supply chain risk management and artificial intelligence: State of the art and future research directions. *International Journal of Production Research*, *57*(7), 2179–2202.

Bloom, N., & Van Reenen, J. (2013). The harmonogram of Karol Adamiecki. *NBER Working Papers*, *18*(2), 89.

Borkowski, A. S. (2023). Evolution of BIM: Epistemology, genesis and division into periods. *Journal of Information Technology in Construction*, *28*, 646–661.

Botta, A., De Donato, W., Persico, V., & Pescapé, A. (2016). Integration of cloud computing and Internet of Things: A survey. *Future Generation Computer Systems*, *56*, 684–700.

Brockmann, C., Brezinski, H., & Erbe, A. (2016). Innovation in construction megaprojects. *Journal of Construction Engineering and Management*, *142*(11), 1–9.

Cao, Q., Zanni-Merk, C., Samet, A., Reich, C., Beuvron, F. de B. de, Beckmann, A., & Giannetti, C. (2022). KSPMI: A knowledge-based system for predictive maintenance in Industry 4.0. *Robotics and Computer-Integrated Manufacturing*, *74*, 102281.

Chen, S., Zeng, Y., Majdi, A., Salameh, A. A., Alkhalifah, T., Alturise, F., & Ali, H. E. (2023). Potential features of building information modelling for application of project management knowledge areas as advances modeling tools. *Advances in Engineering Software*, *176*, 103372.

Cheng, T., & Teizer, J. (2013). Real-time resource location data collection and visualization technology for construction safety and activity monitoring applications. *Automation in Construction*, *34*, 3–15.

Choi, H. W., Kim, H. J., Kim, S. K., & Na, W. S. (2023). An overview of drone applications in the construction industry. *Drones*, *7*(8).

Çinar, Z. M., Nuhu, A. A., Zeeshan, Q., Korhan, O., Asmael, M., & Safaei, B. (2020). Machine learning in predictive maintenance towards sustainable smart manufacturing in Industry 4.0. *Sustainability (Switzerland)*, *12*(19).

Cummins, C., Wasti, B., Guo, J., Cui, B., Ansel, J., Gomez, S., Jain, S., Liu, J., Teytaud, O., Steiner, B., Tian, Y., & Leather, H. (2022). CompilerGym: Robust, performant compiler optimization environments for AI research. In *CGO 2022 - Proceedings of the 2022 IEEE/ACM International Symposium on Code Generation and Optimization* (pp. 92–105). IEEE.

Daniel, C., Hülsheger, U. R., Kudesia, R. S., Sankaran, S., & Wang, L. (2023). Mindfulness in projects. *Project Leadership and Society*, *4*, 100086.

Datta, S. D., Tayeh, B. A., Hakeem, I. Y., & Abu Aisheh, Y. I. (2023). Benefits and barriers of implementing building information modeling techniques for sustainable practices in the construction industry—A comprehensive review. *Sustainability (Switzerland)*, *15*(16).

Durojaye, A., Koolahdoz, A., Nawaz, A., & Moshayedi, A. J. (2023). Immersive horizons: Exploring the transformative power of virtual reality across economic sectors. *EAI Endorsed Transactions on AI and Robotics*, *2*(1), e6.

Eifrig, B. (1972), Ein Nicht-standard-beweis füur die existenz eines starken liftings in l∞ ⟨0, 1]. *Studies in Logic and the Foundations of Mathematics*, *69*(C), 81–83.

Eker, B., & Akdogan Eker, A. (2023). Tips for a successful application of innovation in a business. *Journal of Innovations in Business and Industry*, *1*(1), 47–52. https://doi.org/10.61552/JIBI.2023.01.006

Fells, M. J. (2000). Fayol stands the test of time. *Journal of Management History (Archive)*, *6*(8), 345–360.

Gal, A., Filip, I., & Dragan, F. (2018). A new vision over agile project management in the Internet of Things era. *Procedia - Social and Behavioral Sciences*, *238*, 277–285.

Ghaffarianhoseini, A., Tookey, J., Ghaffarianhoseini, A., Naismith, N., Azhar, S., Efimova, O., & Raahemifar, K. (2017). Building information modelling (BIM) uptake: Clear benefits, understanding its implementation, risks and challenges. *Renewable and Sustainable Energy Reviews*, *75*, 1046–1053.

Ghobakhloo, M., Iranmanesh, M., Foroughi, B., Babaee Tirkolaee, E., Asadi, S., & Amran, A. (2023). Industry 5.0 implications for inclusive sustainable manufacturing: An evidence-knowledge-based strategic roadmap. *Journal of Cleaner Production*, *417*, 138023.

Hardardottir, U. M., & Moller, E. (2023). Success factors in construction project management. *Sylwan*, January.

Hunke, M., & Waibel, A. (1995). Face locating and tracking. In *Human-Computer Interaction* (pp. 1277–1281).

Khanzadi, M., Sheikhkhoshkar, M., & Banihashemi, S. (2020). BIM applications toward key performance indicators of construction projects in Iran. *International Journal of Construction Management*, *20*(4), 305–320.

Khudhair, A., Li, H., Ren, G., & Liu, S. (2021). Towards future BIM technology innovations: A bibliometric analysis of the literature. *Applied Sciences (Switzerland)*, *11*(3), 1–21.

Lawal, O., & Nawari, N. O. (2023). Blockchain and city information modeling (CIM): A new approach of transparency and efficiency. *Journal of Information Technology in Construction*, *28*, 711–734.

Lee, I., & Lee, K. (2015). The Internet of Things (IoT): Applications, investments, and challenges for enterprises. *Business Horizons*, *58*(4), 431–440.

Li, C., Chen, Y., & Shang, Y. (2022). A review of industrial big data for decision making in intelligent manufacturing. *Engineering Science and Technology, an International Journal*, *29*, 101021.

Liao, L., Zhou, K., Fan, C., & Ma, Y. (2022). Evaluation of complexity issues in building information modeling diffusion research. *Sustainability (Switzerland)*, *14*(5).

Liu, Z., Zhang, X., Sun, Y., & Zhou, Y. (2023). Advanced controls on energy reliability, flexibility and occupant-centric control for smart and energy-efficient buildings. *Energy and Buildings*, *297*, 113436.

Ma, Y. P. (2021). Extending 3D-GIS district models and BIM-based building models into computer gaming environment for better workflow of cultural heritage conservation. *Applied Sciences (Switzerland)*, *11*(5), 1–23.

Mahajan, G. (2021). Applications of drone technology in the construction industry: A study 2012-2021. *International Journal of Engineering and Advanced Technology*, *11*(1), 224–239.

Malega, P. (2019). Project management – Standard for today's modern company. *3*(2), 29–35.

Manzoor, B., Othman, I., & Pomares, J. C. (2021). Digital technologies in the architecture, engineering and construction (AEC) industry—a bibliometric—qualitative literature review of research activities. *International Journal of Environmental Research and Public Health*, *18*(11).

Marnewick, C., & Marnewick, A. L. (2020). The demands of Industry 4.0 on project teams. *IEEE Transactions on Engineering Management*, *67*(3), 941–949.

McAllister, C. D., Simpson, T. W., Hacker, K., Lewis, K., & Messac, A. (2005). Integrating linear physical programming within collaborative optimization for multiobjective multidisciplinary design optimization. *Structural and Multidisciplinary Optimization*, *29*(3), 178–189.

Noor, S. R. M. (2020). Critical success factor model framework for lean.

Pan, Y., & Zhang, L. (2021a). Roles of artificial intelligence in construction engineering and management: A critical review and future trends. *Automation in Construction*, *122*, 103517.

Pan, Y., & Zhang, L. (2021b). A BIM-data mining integrated digital twin framework for advanced project management. *Automation in Construction*, *124*.

Parker, L. D. (2014). Corporate social accountability through action: Contemporary insights from British industrial pioneers. *Accounting, Organizations and Society*, *39*(8), 632–659.

Patil, A. G. (2019). Applications of artificial intelligence in construction management. *International Journal of Research in Engineering, IT and Social Sciences*, 9(Special), 21–28.

Picciotto, R. (2020). Towards a 'New Project Management' movement? An international development perspective. *International Journal of Project Management*, *38*(8), 474–485.

Piraveenan, M. (2019). Applications of game theory in project management: A structured review and analysis. *Mathematics*, *7*(9), 858.

Pitsi, S. T. (2018). The competency profile of project managers in Siemens, South Africa–A special focus on personal competencies. *Researchgate.Net*, July.

Provost, F., & Fawcett, T. (2013). Data science and its relationship to big data and data-driven decision making. *Big Data*, *1*(1), 51–59.

Ran, Y., Zhou, X., Lin, P., Wen, Y., & Deng, R. (2019). A survey of predictive maintenance: Systems, purposes and approaches. *arXiv preprint arXiv:1912.07383*, 1-36.

Rane, N. (2023). Integrating building information modelling (BIM) and artificial intelligence (AI) for smart construction schedule, cost, quality, and safety management: Challenges and opportunities. *SSRN Electronic Journal*.

Rao, A. S., Radanovic, M., Liu, Y., Hu, S., Fang, Y., Khoshelham, K., Palaniswami, M., & Ngo, T. (2022). Real-time monitoring of construction sites: Sensors, methods, and applications. *Automation in Construction*, *136*, 104099.

Regona, M., Yigitcanlar, T., Hon, C. K. H., & Teo, M. (2023). Mapping two decades of AI in construction research: A scientometric analysis from the sustainability and construction phases lenses. *Buildings*, *13*(9).

Sarker, I. H. (2021). Data science and analytics: An overview from data-driven smart computing, decision-making and applications perspective. *SN Computer Science*, *2*(5), 1–22.

Schwertner, K. (2017). Digital transformation of business. *Trakia Journal of Science*, *15*(Suppl. 1), 388–393.

Sepasgozar, S. M. E., Khan, A. A., Smith, K., Romero, J. G., Shen, X., Shirowzhan, S., Li, H., & Tahmasebinia, F. (2023). BIM and digital twin for developing convergence technologies as future of digital construction. *Buildings*, *13*(2).

Seymour, T., & Hussein, S. (2014). The history of project management. *International Journal of Management & Information Systems (IJMIS)*, *18*(4), 233.

Shi, Q., & Abdel-Aty, M. (2015). Big data applications in real-time traffic operation and safety monitoring and improvement on urban expressways. *Transportation Research Part C: Emerging Technologies*, *58*, 380–394.

Siccardi, S., & Villa, V. (2023). Trends in adopting BIM, IoT and DT for facility management: A scientometric analysis and keyword co-occurrence network review. *Buildings*, *13*(1).

Suermann, P. C. (2009). *Evaluating the impact of building information modeling (BIM) on construction*. University of Florida.

Taboada, I., Daneshpajouh, A., Toledo, N., & de Vass, T. (2023). Artificial intelligence enabled project management: a systematic literature review. *Applied Sciences*, *13*(8), 5014.

Tan, S. Y., & Taeihagh, A. (2021). Governing the adoption of robotics and autonomous systems in long-term care in Singapore. *Policy and Society*, *40*(2), 211–231. Routledge.

Tang, L., Liu, J., Rong, A., & Yang, Z. (2001). A review of planning and scheduling systems and methods for integrated steel production. *European Journal of Operational Research*, *133*(1), 1–20.

Tang, S., Shelden, D. R., Eastman, C. M., Pishdad-Bozorgi, P., & Gao, X. (2019). A review of building information modeling (BIM) and the Internet of Things (IoT) devices integration: Present status and future trends. *Automation in Construction*, 101, 127–139.

Tsygankov, N., Tukkel, I., & Moskalev, A. (2023). The peculiarity of planning the production of innovative products. *Journal of Engineering, Management and Information Technology*, *1*(2), 85–94. doi: 10.61552/JEMIT.2023.02.005

Unegbu, H. C. O., Yawas, D. S., & Dan-asabe, B. (2021). Assessment of the relative im-portance and relationships of project management practices for the construc-tion industry in Nigeria. *Proceedings on Engineering Sciences*, *3*(1), 65-80. doi: 10.24874/PES03.01.007

Valavanidis, A., & Valavanidis, A. (2020). Universities as innovation drivers for major disruptive technological transformations and economic development. Retrieved from https://chem-tox-ecotox.org/ScientificReviews

Xue, X., Zhang, R., Yang, R., & Dai, J. (2014). Innovation in construction: A critical review and future research. *International Journal of Innovation Science*, *6*(2), 111–125.

Yan, J., Meng, Y., Lu, L., & Li, L. (2017). Industrial big data in an Industry 4.0 environment: Challenges, schemes, and applications for predictive maintenance. *IEEE Access*, *5*, 23484–23491.

Yang, W. H., & Tarng, Y. S. (1998). Design optimization of cutting parameters for turning operations based on the Taguchi method. *Journal of Materials Processing Technology*, *84*(1–3), 122–129.

Zhu, J., & Mostafavi, A. (2017). Discovering complexity and emergent properties in project systems: A new approach to understanding project performance. *International Journal of Project Management*, 35(1), 1–12. Elsevier Ltd and Association for Project Management and the International Project Management Association.

Zonta, T., da Costa, C. A., da Rosa Righi, R., de Lima, M. J., da Trindade, E. S., & Li, G. P. (2020). Predictive maintenance in the Industry 4.0: A systematic literature review. *Computers and Industrial Engineering*, 150, 106889. Elsevier Ltd.

Houljakbe Houlteurbe Dagou
Yildiz Technical University,
Department of Civil Engineering,
Istanbul, Türkiye
dagoucharles@gmail.com
ORCID 0000-0003-1249-2615

Asli Pelin Gurgun
Yildiz Technical University,
Department of Civil Engineering,
Istanbul, Türkiye
apelin@yildiz.edu.tr
ORCID 0000-0002-0026-4685

Kerim Koc
Yildiz Technical University,
Department of Civil Engineering,
Istanbul, Türkiye
kerimkoc@yildiz.edu.tr
ORCID 0000-0002-6865-804X

Handan Kunkcu
Eskisehir Technical University,
Department of Civil Engineering,
Eskisehir, Türkiye
handan424@eskisehir.edu.tr
ORCID 0000-0001-9839-640X